

**WYOMING DEPARTMENT OF TRANSPORTATION BRIDGE PROGRAM**

Anticipated Steel Girder Construction FY 2021

Design Project Number	Route	Tentative Letting Date	Feature	Bridge Specifics			
				Type	Length (ft)	Width (ft)	No. of Girder Lines
CN01065	Natrona County Road	11/13/2020	Bates Creek	SS Comp. WP	85.00	29.34	4
CN01064	Natrona County Road	12/9/2020	Bridge Over BNSF	3 Span Cont. WP	195.00	30.34	4
I802220	Rock Springs	12/9/2020	Bridge Over I-80	3 Span Cont. Comp. WP	250.00	62	7
2202021	Worland - Manderson	12/9/2020	Worland Canal	SS Comp. WP	60.00	35.34	5
2202021	Worland - Manderson	12/9/2020	10 Mile Creek	SS Comp. WP	125.00	35.34	4
2202021	Worland - Manderson	12/9/2020	Worland Canal	SS Comp. WP	55.00	35.34	5
B123014	Rock Springs	12/9/2020	Bridge Over UPRR	4 Span Cont. Comp. WP	390.00	44.34	5
N212121	Casper Streets	1/14/2021	North Platte River	5 Span Cont. Comp. WP BW	341.00	*74.25	9
I254160	Casper Streets	5/6/2021	Walsh Drive	7 Span Cont. Comp. WP	960.00	88.34	9
I802208	Rock Springs - Rawlins	7/8/2021	Baxter Interchange	3 Span Cont. Comp. WP	145.00	41.34	5
**P114038	La Barge - Big Piney	7/8/2021	Wildlife Crossing	41' W x 11.75' H Arch	52.00	NA	NA
N372041	Ranchester Streets	8/12/2021	BNSF Overpass	3 Span Cont. Comp. WP	435.00	45.75	6

\* Widened Width

\*\*Arch will be bid as alternate precast concrete or metal

Cont. = Continuous	BW = Bridge Widening
Comp. = Composite	WP = Welded Plate
SS=Simple Span	
WF = Wide Flange	
W = Width of Box Opening	
H = Height of Box Opening	